

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Arenac Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

- |                                      |             |              |             |  |           |
|--------------------------------------|-------------|--------------|-------------|--|-----------|
| 1. Public Land Survey                | T _____     | R _____      |             |  |           |
|                                      | T _____     | R _____      |             |  |           |
| 2. Property Controlling in Section   | S <u>12</u> | T <u>19N</u> | R <u>4E</u> |  | <u>11</u> |
|                                      | S <u>12</u> | T <u>19N</u> | R <u>4E</u> |  | <u>15</u> |
| 3. Miscellaneous Property in Section | S _____     | T _____      | R _____     |  |           |
|                                      | S _____     | T _____      | R _____     |  |           |

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on January 8, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

11 – CSR – Lg. Bk. P. 37 – G.F. Carscallen – 1900  
 Set Post

15 – CSR – Lg. Bk. P. 37 – G.F. Carscallen – 1900  
 Post



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

11 – SW 1/16 Cor., Sec. 12, T19N, R4E  
 No evidence of Carscallen Post.  
 Set 2" Alum. Cap on 5/8" x 34" Rebar per standard BLM procedure. Corner of single strand wire W & S is 60'+ S & 65'+ E.

15 – W 1/16 corner common to Sec. 12 & 13, T19N, R4E – no conclusive evidence of Carscallen post found. Set 2" Alum. Cap on 5/8" x 34" Rebar per standard BLM procedure. Corner of single strand wires N,S, E & W is 13'+ W & 26'+ S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

11 – 2" AC on 5/8" X 34" Rebar  
 NE 1' to set Blue Carsonite Post with location tag  
 N45°E 14.68' to N & T in N side 4" R. Maple scribed 'XBT'  
 S84°E 11.61' to N&T in SW side 6" R. Maple scribed 'XBT'  
 S28°W 39.02' to N&T in W side 8" Oak  
 N62°W 24.53' to NE & T in NE side 6" R. Maple

15 – 2" AC on 5/8" x 34" Rebar  
 NE 1' to set Blue Carsonite post with location tag  
 N60°E 39.68' to N&T in NW side 20" W. Pine  
 S72°E 64.11' to N&T in N side 10" W. Pine  
 N25°W 42.78' to N&T in SW side 8" Oak  
 S33°W 30.49' to Fd. 1 1/2" iron pipe filled w/ conc.

Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 3/4/2002