

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Arenac Located In _____ Corner Code # _____
 (County)

1. Public Land Survey T _____ R _____
 T _____ R _____

2. Property Controlling in Section S 13 T 19N R 4E 7
 S 13 T 19N R 4E 14

3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on December 4, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
7 - None 14 - None



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:
7 - N 1/16 Cor. common to Sec. 13, T19N, R4E & Sec. 18, T19N, R5E - set 2" Alum. cap on 5/8" x 34" rebar per standard BLM procedure. Corner of single strand fence E & S is 16' W & 19' N.
14 - S 1/16 Cor. common to Sec. 13, T19N, R4E & Sec. 18, T19N, R5E - set 2" Alum. cap on 5/8" x 34" rebar per standard BLM Procedure. Centerline of N-S Gravel Rd. is 2' W. Fence Remains E & W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
7 - 2" AC on 5/8" x 34" rebar
 NW 1' to set Blue Carsonite Post w/ loc. tag
 N40°E 47.36' to set N & T in NW side 16" R. Oak
 N73°E 54.03' to set N & T in S side 22" W. Pine
 S83°E 28.27' to set N & T in N side 8" Cedar
 S39°W 43.14' to set N & T in NW side 7" Cedar
 N39°W 24.05' to face 8" Cedar Cor. Fence Post - E & S
14 - 2" Alum. Cap on 5/8" x 34" rebar - Down 0.5'
 West 33.00' to set 2" Alum. Cap on 5/8" x 34" rebar on line w/ Blue Carsonite Post w/ loc. tag
 N70°W 41.97' to set N & T in S side 20" Ash
 N38°W 50.65' to set N & T in NE side 20" W. Oak
 S70°E 67.69' to set N & T in S side 8" Hemlock
 S54°09'W 5.82' to Fd. Bent 1/2" Rebar

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 3/4/2002