

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_  
Arenac \_\_\_\_\_  
(County) \_\_\_\_\_

1. Public Land Survey	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S <u>13</u>	T <u>19N</u>	R <u>4E</u>
	S _____	T _____	R _____
3. Miscellaneous Property in Section	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on January 3, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

12 – None

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

12 – CS 1/16 cor. Sec. 13, T19N, R4E – Set 2" Alum. Cap on 5/8" x 34" Rebar per standard BLM procedure. Corner of fences N, S, E & W is 1.5' E & 4.5' S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

12 – 2" AC on 5/8" X 34" Rebar  
NE 1' to set Blue Carsonite Post with location tag  
N27°E 9.89' to N & T in E side 10" Oak  
S83°E 50.16' to N&T in N side 20" Oak  
S40°W 14.02' to N&T in E side 3" Oak  
S48°E 25.71' to N & T in SW side 12" Sco. Pine



Signed by: Craig W. McVean  
Surveyor's Michigan License No.: 39088

Date: 3/4/2002