

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 19 N. R. 5	E-1; E-2; F-1
2. PROPERTY CONTROLLING IN SECTION 4.....	T. 19 N. R. 5	2
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. R. E. S. R. W.	
4. LOT NO. _____, RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 17, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A - Description of original monument and accessories and or subsequent restoration.~~

C. (continued)

	2	
Set 5/8" Rod w/RLS Cap & Cedar Post		
9" Maple	S78°E	24.48
2" Maple	S51°W	15.83

B. Description of corner evidence found and or method applied in restoring or re-establishing corner.

- 1 Set corner relative to standard corner, according to U.S. record and G. H. Hollister 1910 survey.
- 2 Set corner by proportionate measurement between section corners. No previous corner found. Hunting wire fence intersection is about 128' SW'ly and too far off to be considered a valid location for corner.
- 1 Set by single proportionate measurement between section corners.
- 2 Set corner by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

E-1	E-2	F-1
Set DNR Monument	Set DNR Monument	Set DNR Monument
7" Oak S17°W 25.91	8" R. Oak N85°W 22.64	3" Oak S15°E 16.15
5" Oak S76°W 66.54	7" R. Oak S23°W 28.55	6" J. Pine S88°W 59.0
Corner to 32-33, T20N-R5E		S ¹ / ₄ corner Sec. 33 T20N-R5E
is N89°49'30"E 7.3		is N89°49'30"E 23.5

SIGNED BY *Kenneth J. Ostling*
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

DATE _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____
CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE _____



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

ARENAC COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN 20, 1971
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET