

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T 19 N R. 5 1		D-1; G-1
2. PROPERTY CONTROLLING IN SECTION 5 T 19 N R. 5 1		7
3. MISCELLANEOUS PROPERTY IN SECTION _____ T _____ S. R. _____ W.		
4. LOT NO. _____ RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER _____

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 17, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

- 1 Set corner by single proportionate measurement and relative to standard corners, according to G. H. Hollister 1910 survey of record.
- 1 Set closing corner as prescribed by U.S. survey record, relative to the standard corner.
- 7 Set by proportionate measurement according to standard survey procedures for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

D-1	G-1	7
Set DNR Monument	Set DNR Monument	Set 5/8" Rod w/RLS Cap
11" W. Oak S33°E 10.6	11" Birch S02°E 4.65	4" Oak S34°E 8.66
7" Oak S67°W 18.33	8" Oak S54°W 24.55	11" Oak S85°W 20.64
S½ cor Sec. 32 T20N-R5E is	Cor to 33 & 34 T20N-R5E is	
N89°49'30"E 3.65	N89°49'30"E 39.6	

SIGNED BY Kenneth J. Ostling

DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

DATE _____

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ ARENAC COUNTY