

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>19</u> ^{N.} / _{S.} , R. <u>5</u> ^{E.} / _{W.}	<u>G-3</u>
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	T. <u>19</u> ^{N.} / _{S.} , R. <u>5</u> ^{E.} / _{W.}	<u>9, 7, 12</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} / _{S.} , R. _____ ^{E.} / _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 28, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:


A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- G-3 Set corner by single proportionate measurement between 1/4 corners east and west. Fits swamp edge north and other occupation in Sec. 4. No previous corner evident.
 - 9 Set corner by standard survey procedure for the subdivision of sections.
 - 7 Set corner by standard survey procedure for the subdivision of sections.
 - 12 Set corner by standard survey procedure for the subdivision of sections.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | | |
|----------------------------|-------------------------------------|-------------------------------------|
| G-3 | 9 | 7 |
| Set DNR Mon. | Set 5/8" rod with cap & cedar post. | Set 5/8" rod with cap & cedar post. |
| 6" B. Ash N49°E 23.4 ft. | 5" J. Pine N33°E 7.6 ft. | 7" J. Pine S22°E 32.0 ft. |
| 6" R. Maple S10°W 19.3 ft. | 12" J. Pine N37°W 29.6 ft. | 9" J. Pine N33°W 19.6 ft. |
-
- | |
|-------------------------|
| 12 |
| Set 5/8" bar w/cap |
| 5" cedar S68°W 13.6 ft. |
| 7" cedar S07°E 23.2 ft. |

SIGNED BY Kenneth J. Ostling SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

DATE 8/20/81



FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ ARENAC COUNTY