

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 19 N. R. 5 E.	G-2, F-2
2. PROPERTY CONTROLLING IN SECTION 4 _____	T. 19 N. R. 5 E.	15, 11
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
 FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 28, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-2 Set corner by single proportionate measurement between section corners. Could find no evidence of a previous corner.
- 15 Set corner by standard survey procedure for the subdivision of sections.
- 11 Set by standard survey procedure for the subdivision of sections.
- F-2 Set by standard survey procedure, at the calculated intersection of the true 1/4 lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2	15	11
Set 5/8" iron bar w/RLS cap	Set 5/8" re-rod with cap	Set 5/8" re-rod w/cap
8" R. Oak N24°E 3.6 ft.	6" Cedar N24°E 12.8 ft.	10" Cedar S09°E 10.1 ft.
7" R. Oak S22°E 4.6 ft.	14" Cedar S89°E 30.4 ft.	8" Cedar N80°E 16.2 ft.

F-2

Set 5/8" rod w/cap & cedar post.
 5" W. Pine S49°E 12.0 ft.
 10" R. Oak S49°W 43.6 ft.

SIGNED BY Kenneth J. Ostling DATE 8/20/81

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ ARENAC COUNTY