

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac Located In _____ Corner Code # _____
(County)

1. Public Land Survey T 20N R 3E G13
T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Aug. 18, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G13 – GLO – Set Post – L. Clason – 1837
Pine 4" S75½°W 24 L.
Tamarack 5" N71°W 50 L.
- MDOT Wit. Card – C. F. Roser – 1965
(LCRC – L. 1, p. 230 – 1984) – Set 2" pipe –
5' long with 12" above ground. Marked Cedar guard
post. Corner set by single proportion between fd. Corners
E & W. 5" Poplar N14°E 38.14'; 6" Poplar N65°W 52.62';
N89° 52' 50" E 30.43' to 'G1', T19N, R3E.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G13 – Standard Corner common to Sec. 33 & 34, T20N, R3E – Fd. 2" iron pipe – Up 2' – per MDOT in swamp. No GLO evidence.
All MDOT BT's gone. Fits MDOT Survey dimensions. 2" pipe accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G13 – Drove stamped 2" Alum. Cap on 5/8" x 5' long iron rebar into centerline of Fd. 2" pipe
Set Blue Carsonite Post 1' N
East 30.49' (30.36' – GLO) to 'G1', T19N, R3E – 2" Alum. Cap in 2" pipe
N65°W 34.68' to set ½" x 30" rebar
S14°E 47.85' to set ½" x 2.7' rebar
N24°E 48.20' to set ½" x 30" rebar



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 2/7/2005