

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey	T	<u>20N</u>	R	<u>3E</u>	<u>H13</u>
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Aug. 18, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

H13 – GLO – Set ¼ Post – L. Clason – 1837  
 Tamarack 2 ½" N20°E 22 L.  
 Pine 3" N16½°W 17 L.  
 - MDOT Wit. Card – C. F. Roser – 1965  
 (LCRC – L. 1, p. 228 – 1984) – Set 2" pipe;  
 4' long with 13" above the ground. Marked cedar guard post. Corner set by single prop. between fd. corners E & W. N89° 52' 50" E. 28.41' to 'H1', T19N, R3E.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H13 – Standard ¼ Corner common to Sec. 34, T20N, R3E – Fd. 2" iron pipe – Up 1.3' – per MDOT in swamp. No GLO evidence. 2" iron pipe accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H13 – Drove stamped 2" Alum. Cap on 5/8" x 4' long iron rebar into centerline of fd. 2" pipe.  
 Set Blue Carsonite Post 1' N.  
 N13°E 15.70' to set N & T in E side 2" Tw. R. Maple scribed 'XBT'  
 N79°W 17.32' to set N & T in S side 10" Tamarack scribed 'XBT'  
 S10°W 17.69' to set N & T in E side 2" Ash  
 East 28.42' to 'H1', T19N, R3E – 2" Alum. Cap in 2" pipe



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 2/7/2005