

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 20N R 3E F10  
 T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Aug. 11, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- F10 - CSR - FB #14, P. 53 - 1915 - Set; 39.78 to 'F9'; 40 to 'F11'; 40.63 to 'G10' 40.23 to 'E10'
- MDOT Wit. Card - C. F. Roser - 1965 (LCRC - L. 1, p. 239 - 1984) Set 4' of 1" pipe on line between 1/4 corners N-S and E-W. Mark cedar guard post. This corner fits calls in old survey notes by Hollister - Co. Sur. 1915 15" R. Pine S85°W 86.04'; 14" R. Pine N50°W 32.35'; 10" J. Pine N15°W 46.42'; 10" Oak S85°E 88.53'
- Rec. Suv - L. 1, p. 508 - L. D. McGinnis - 1984 - 1" pipe - Same wit's. as MDOT.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F10 - C 1/4, Sec. 28 - Fd. Bent 1" Iron pipe per MDOT on W'ly edge of I-75 drainage ditch on SW'ly side of I-75. Fits intersection of 1/4 line closely. Bent 1" Iron pipe accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F10 - Cut off top bent 1.6' of 1" pipe and drove stamped 2" Alum. Cap on 5/8" x 34" iron rebar into centerline of 1" pipe bottom.  
 Set Blue Carsonite Post 1' E  
 N49°W 32.10' to set N & T in NE side 19" R. Pine (MDOT, LDM)  
 N18°E 19.36' to set N & T in E side 18" Oak  
 N68°E 13.61' to set N & T in S side 5" J. Pine  
 S60°W 60.72' to set N & T in N side 9" R. Pine



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 2/7/2005