

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac (County)	Located In	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>3E</u>	<u>G12</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Aug. 16, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			1
3													
4	7			8			9			10			12
5													
6	18			17			16			15			13
7													
8	19			20			21			22			24
9													
10	30			29			28			27			25
11													
12	31			32			33	●		34			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G12 – GLO – Set ¼ Post – John Mullet – 1846
Tamarack 6" N12°E 17 L.
Tamarack 5" S8°E 26 L.
- MDOT Wit. Card – C. F. Roser – 1965
(LCRC – L. 1, p. 234 – 1984)
Set 2" pipe – 4' long – 2' above ground by single proportion
between Sec. Corners N & S.
Mark Cedar guard stake, 20" Elm S75°W 125.06';
8" Poplar S85°W 97.37'; 11' Ash N50°E 107.03'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G12 – ¼ Corner common to Sec. 33 & 34 – Fd. rusted off 2" Iron pipe in cattail swamp per MDOT. MDOT Wit's are gone but fits their survey dimensions. Corner between N & S bound lanes of I-75. SSE 3.4' found 3" Cedar post. 2" pipe accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G12 – Drove stamped 2" Alum. Cap on 5/8" x 34" iron rebar into centerline of Fd. 2" pipe.
Set Blue Carsonite Post 1' N
N75°E 74.11' to set N & T in N. side 16" Willow
S57°W 27.51' to set ½" x 24" rebar
S41°E 30.11' to set ½" x 2.7' rebar
N2°W 28.39' to set ½" x 30" rebar



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 2/7/2005