

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac Located In _____ Corner Code # _____
 (County)

1. Public Land Survey	T _____	R _____		
	T _____	R _____		
2. Property Controlling in Section	S <u>29</u>	T <u>20N</u>	R <u>3E</u>	<u>4</u>
	S <u>29</u>	T <u>20N</u>	R <u>3E</u>	<u>8</u>
3. Miscellaneous Property in Section	S _____	T _____	R _____	
	S _____	T _____	R _____	

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on June 15, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		● 29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

4 - Consumer's Drawing No. - S. F. 16944, Sheet 96 - 1968 - 'T' iron set with CP Co. Cap.

8 - Consumer's Drawing No. - S. F. 16944, Sheet 96 - 1968 - 'T' iron set with CP Co. Cap.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

4 - NW 1/16 Cor., Sec. 29 - No evidence of Consumers 'T' iron. Set stamped 2" Alum. Cap on 5/8" x 34" iron rebar per Standard BLM procedure. Falls on E'ly edge of Powerline clearing.

8 - CW 1/16 Cor., Sec. 29 - No evidence of Consumers 'T' iron. Set stamped 2" Alum. Cap on 5/8" x 34" iron rebar per Standard BLM procedure. Falls on E'ly edge of Powerline clearing.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4 - Stamped 2" Alum. Cap on 5/8" x 34" rebar
 S70°E 48.23' to N & T in N. side 16" R. Maple
 S37°E 35.87' to N & T in SW side 8" R. Maple
 S23°W 32.82' to Fd. 1/2" rebar
 N24°E 12.04' to N & T in E. side W. Birch
 Set Blue Carsonite Post with loc. tag 1' SE

8 - Stamped 2" Alum. Cap on 5/8" x 34" rebar
 S86°W 41.52' to N & T in N. side P.P.
 N23°E 30.95' to N & T in E. side 14" J. Pine
 S62°E 17.31' to N & T in N. side 8" Tamarack
 S32°E 24.44' to N & T in SW side 9" Tamarack
 Set Blue Carsonite Post with Loc. Tag 1' E

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/30/2005

