

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Arenac Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S 30 T 20N R 3E 6  
 S 30 T 20N R 3E 8

3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on June 20, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
6 - None 8 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

6 - NE 1/16 Cor., Sec. 30 - Set stamped 2" Alum. Cap on 5/8" x 34" iron rebar per Standard BLM procedure.

8 - CW 1/16 Cor., Sec. 30 - Set stamped 2" Alum. Cap on 5/8" x 34" iron rebar per Standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar  
 Set Blue Carsonite Post with loc. tag 1' SW  
 S84°E 3.30' to set N & T in N. side 10" R. Maple  
 S42°W 13.95' to set N & T in E. side 8" R. Maple  
 N33°W 42.79' to set N & T in NE side 9" R. Maple  
 S52°E 8.97' to set N & T in N. side 8" Elm

8 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar.  
 Set Blue Carsonite Post with loc. tag 1' SE  
 N16°E 39.18' to set N & T in NW side 4" W. Pine  
 S80°E 13.05' to set N & T in N. side 6" Oak  
 S2°W 26.76' to set N & T in W. side 8" Oak  
 S38°W 12.17' to set N & T in NW side 6" R. Maple

Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 11/30/2005