

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Arenac
 (County)

Located In _____ Corner Code # _____

| | | | | | | |
|--------------------------------------|---|---|-----|---|----|-----|
| 1. Public Land Survey | | T | 20N | R | 4E | M11 |
| | | T | 20N | R | 5E | A11 |
| 2. Property Controlling in Section | S | T | | R | | |
| | S | T | | R | | |
| 3. Miscellaneous Property in Section | S | T | | R | | |
| | S | T | | R | | |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on August 1, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| <p><u>A11 & M11</u> – GLO – Set post – L. Clason – 1837 Lynn 6" S67°W 26 L. W. Birch – N74°E</p> <p>- GLO – T20N, R5E – Sub. – B.F. Hall – 1846 Birch 10" N73°E 12 L. Birch 6" S61°E 17 L.</p> <p>- CSR – BK. 6, P. 47 - 1906 - CSR – BK. 16, P. 25 – 1921 - Post - MDOT – 1957 – Fd. 4" X 4" Wood stake Set 1" iron bar; N67°W 4" Oak 74.44'; S57°E 6" Poplar 59.71'; S69°W 9" Oak 59.67'</p> | <p>- Rec. Sur. L.1, Pg. 491- 1983 - R.L. Miller R.R. Spike – N45°W 54.20' PP; S60°W 62.20' – 14" Oak</p> <p>- Rec. Sur. – L.2, P. 137 – 1995 – R.L. Miller Fd. R.R. Spike</p> |
|--|---|

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

A11 & M11 – Sec. corner common to Sec. 25 & 36, T20N, R4E & Sec. 30 & 31, T20N, R5E – Fd. 1" x 1' long tapered round bar w/ threads with 2" x 2" x 6" wood stake on N. side & 3" x 3" x 12" cedar stake w/ axed pt. on S. side – down 1'. Dug down 2' and also find old plow point below. All of MDOT's BT's are gone but this agrees with MDOT's description of corner monument. CL of N-S Gravel Rd. is 1'+ W. CL of Gravel Rd. W is 9' N. On CL of Gravel Rd. E extended W'ly. 1" iron bar per MDOT accepted as the best available evidence of the position of the original corner.

Reference Pt. 'A' – Fd. R.R. Spike N8°51'W 5.90' of "A11-M11" per Miller's Rec. Survey L. 1, P. 491 Witnesses. Excavated position but no other evidence to support position was found. RR Spike used by Miller not utilized as "A11-M11" in this survey – removed.

Reference Pt. 'B' – Fd. 2nd R.R. Spike N6°12'E 4.60' of "A11-M11" that fits Miller's Rec. Sur. L. 2, P. 137 based on his record distance to K11. Excavated location but no other evidence to support position was found. 2nd R.R. Spike not utilized as "A11-M11" in this survey – removed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A11 & M11 – Replaced 1" x 1' iron rod w/ 3" Arenac Co. Remon. Brass Cap on 5/8" x 34" Rebar w/ 4" x 1' long PVC filled w/ conc. around cap – Down 0.5'.
 Placed 2 Fd. stakes & plow pt. at base of monument as memorials.
 S60°E 57.05' to set N & T in NE side 3" Fir
 S72°W 61.13' to set N & T in N side 22" B. Oak (RLM)
 N45°W 59.57' to Fd. N & Tag #15397 in NW side UP (RLM)
 N36°E 86.88' to set N & T in NW side 7" B. Oak



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/13/2001