

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:			
<u>Arenac</u>	<u>Located In</u>	<u>Corner Code #</u>	
(County)			
1. Public Land Survey	T <u>20N</u> R <u>4E</u>	<u>L-11</u>	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11											●		
12	31	32	33	34	35	36							
13													

I, Craig W. McVean, in a field survey on December 19, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L11 - GLO - Set 1/4 post - John Mullett-1846
 Beech 12" S19°W 3.5 links
 Cedar 6" N28°E 20 links
 - CSR - Lg. Bk., P. 13-14 - G.F. Carscallen - 1902
 Sec. 25 Survey.
 - CSR - FB 16. P. 24-27- 1927
 - Recorded survey L. 2, P. 137, -R.L. Miller-1995
 Corner shown midway and online between K-11 and M-11

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L11 - 1/4 corner common to Sec. 25 & 36 - could find no conclusive evidence of corner. No N-S occupation. Set 3" Arenac Co. Remon. Brass cap on 5/8" x 34" Rebar at single proportional position between K11 & M11. Fits position of N-S fence at W 1/16 corner position. CL of E-W Gravel Rd. is 8' N. Measure E. 105'+ (95'-GLO) to W. side of stream crossing under road. Arenac Co. Mon. accepted as a careful & faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L11 - 3" Arenac Co. Remon. Brass Cap on 5/8" x 34" Rebar w/ 4" x 1" PVC filled w/ conc. around cap - Down 0.5'
 South 33.00' to set 2" Alum. Cap on 5/8" x 34" Rebar w/ Blue Carsonite Post w/ loc. tag
 S56°E 54.12' to N & T in SW side 7" Cedar scribed 'XBT'
 S36°E 46.45' to N & T in SW side 7" Oak scribed 'XBT'
 S8°W 35.71' to N & T in W side 5" R. Maple



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 1/14/2002