

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:			
<u>Arenac</u>	Located In	Corner Code #	
(County)			
1. Public Land Survey	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S <u>36</u> T <u>20N</u> R <u>4E</u>		12
	S <u>36</u> T <u>20N</u> R <u>4E</u>		13
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on January 10, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| <p><u>12</u> – Rec. Survey – L. 2, P. 137 – R. L. Miller
– 1995 – shows corner.</p> | <p><u>13</u> – Rec. Survey – L. 2, P. 137 – R. L. Miller
– 1995 – shows corner.</p> |
|---|---|

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- | | |
|---|--|
| <p><u>12</u> – CS 1/16, Sec. 36 – No. evidence of Miller iron.
Appears Rec. Survey shows only calculated position.
Set 2" Alum. Cap on 5/8" x 32" rebar per standard BLM procedure.</p> | <p><u>13</u> – SE 1/16, Sec. 36 – No evidence of Miller iron here. Appears Rec. Survey is only calculated position. Set 2" Alum. cap on 5/8" x 32" Rebar per standard BLM procedure, N15°E 7.65' to Fd. Iron 'U' post at apparent old fence corner of down fences N & E.</p> |
|---|--|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| <p><u>12</u> – 2" Alum. Cap on 5/8" x 32" rebar
NW 1' to set Blue Carsonite Post w/ loc. tag
N62°W 8.35' to N & T in NE side 4" R. Maple scribed 'XBT'
S86°E 10.48' to N & T in N side 3" R. Maple scribed 'XBT'
S20°E 13.73' to N & T in E side 6" Oak
S75°W 58.48' to N & T in N side 20" W. Oak</p> | <p><u>13</u> – 2" Alum. Cap on 5/8" x 32" rebar
NW 1' to set Blue Carsonite Post w/ loc. tag
N16°E 26.65' to N & T in W side 10" Oak scribed 'XBT'
S82°W 24.04' to N & T in S side 4" R. Maple scribed 'XBT'
S35°E 8.22' to N & T in NE side 3" Oak
S10°E 48.77' to N & T in W side 12" W. Pine</p> |
|--|---|

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 3/4/2002

