

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac Located In _____ Corner Code # _____
(County)

1. Public Land Survey T _____ R _____
T _____ R _____

2. Property Controlling in Section S 36 T 20N R 4E 7
S 36 T 20N R 4E NN 1/64

3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on December 3, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
7 - None NN 1/64 - None



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:
7 - N 1/16 Cor. common to Sec. 36, T20N, R4E & Sec. 31, T20N, R5E - set 2" Alum. cap on 5/8" x 34" rebar per standard BLM procedure. Centerline of N-S Gravel Rd. is 16.5'± E. NN 1/64 - Cor. common to Sec. 36, T20N, R4E & Sec. 31, T20N, R5E and being the NE Cor. of the S 1/2 of NE 1/4, Sec. 36, T20N, R4E - Set 2" Alum. cap on 5/8" x 34" rebar per standard BLM procedure, centerline of N-S Gravel Rd. is 8' E. Remains of fence W. is 39'± S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
7 - 2" AC on 5/8" x 34" rebar - Down 0.5' East 50' to set Blue Carsonite Post w/ loc. tag N61°W 22.71' to N & T in S side 3" W. Oak S41°W 27.40' to N & T in SE side 4" W. Oak S64°E 81.96' to N & T in NE side 9" W. Oak S85°E 47.36' to N & T in S side 10" W. Pine NN 1/64 - 2" AC on 5/8" x 34" rebar - Down 0.5' West 25' to set Blue Carsonite Post w/ loc. tag S30°W 44.02' to N & T in SE side 22" W. Oak S73°W 52.88 to N & T in S side 5" Cedar N35°W 35.79' to N & T in SW side 16" Cedar N86°E 68.51' to N & T in S side 10" Cedar

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 3/4/2002