

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>20</u> N. <u>●</u> , R. <u>5</u> E. <u>●</u>	<u>G-8; H-8; I-7</u>
2. PROPERTY CONTROLLING IN SECTION <u>21</u>	, T. <u>20</u> N. <u>●</u> , R. <u>5</u> E. <u>●</u>	<u>2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 21, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 8 Restored corner at stump remains of Govt. corner tree as identified by Co. surveyor in 1911 survey of Sec. 22. Stumps in place for both Co. sur. NBT's & fits measurements of record for Sec. 22.
- 8 Set at calculated intersection of true 1/4 lines, according to standard survey procedure.
- 7 Set corner from stumps of NBT, of record in 1911 survey. Fd. squared post lying down in this area but could not locate bottom. Corner fits record for direction and measurements N-S-E-W.
- 2 Set corner by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8	H-8	I-7
Set DNR mon. & red-top post	Set 5/8" iron bar w/cap and cedar post	Set DNR mon. & cedar post
3" W. Pine N28°W 30.05	6" Birch N07°E 24.6	9" Cedar S70°E 25.1
2" W. Pine N85°E 25.6	4" Maple N77°E 26.3	4" Cedar S22°W 39.4
6" W. Oak S03°W 9.2		
		2
		Set 5/8"x40" iron bar w/cap and cedar post
		6" H. Maple S30°W 2.1
		5" H. Maple S62°E 14.8

SIGNED BY Kenneth J. Ostling DATE Jan 1978

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

ARENAC COUNTY