

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>15</u>	T. <u>20</u> N. R. <u>5</u> E.	<u>5; 14</u>
3. MISCELLANEOUS PROPERTY IN SECTION <u>15</u>	T. <u>20</u> N. R. <u>5</u> E.	<u>H-5/5</u>
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 11, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on January 5, 1978, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 5 Set by standard survey procedure for the subdivision of sections.
- 14 Set by standard survey procedure for the subdivision of sections. Falls about 22' west of corner fence post.
- H-5/5 Set on 1/4 line at 657.52' south of N 1/4 corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5	14	H-5/5
Set 5/8" Rod w/RLS Cap & Cedar Post	Set 5/8" Rod w/RLS Cap & Cedar Post	Set 5/8" Rod w/RLS Cap & red-top Post
14" W. Pine S30°W 30.35	8" W. Pine N32°W 10.5	3" Maple S08°W 26.35
5" Maple S46°E 6.35	4" Cedar S66°E 15.65	5" W. Pine S38°W 19.1

SIGNED BY Kenneth J. Ostling DATE 8/1/78
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ ARENAC COUNTY