

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T 20 N R. 5	D-13; E-13; F-13
2. PROPERTY CONTROLLING IN SECTION 32	T 20 N R. 5	15
3. MISCELLANEOUS PROPERTY IN SECTION	T	
4. LOT NO. RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 17, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or by a Decree of a Court of law:

C. (continued)

15
Set 5/8" Iron Bar w/RLS Cap
5" Oak N44°W 14.49
5" Oak N55°E 38.79

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner
- 13 Set corner by single proportionate measurement according to G. H. Hollister 1910 survey of record. No previous corner found.
 - 13 Set corner by single proportionate measurement according to Hollister 1910 survey of record. No previous corner found.
 - 13 Corner set by proportionate measurement between section corners and falls in center of N-S trail road.
 - 15 Set corner by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

D-13	E-13	F-13
Set DNR Monument	Set DNR Monument	Set DNR Monument
7" Oak N50°W 29.20	3" Poplar N17°E 11.95	5" J. Pine N48°W 22.05
6" Oak N49°E 13.18	3" Poplar N66°E 13.62	4" J. Pine N59°E 15.11
N $\frac{1}{4}$ cor Sec. 5 T19N-R5E is	Cor to 5-4 T19N-R5E is	N $\frac{1}{4}$ cor Sec. 4 T19N-R5E is
S89°49'30"W 3.65	S89°49'30"W 7.3	S89°49'30"W 23.5



SIGNED BY Kenneth J. Ostling
SURVEYOR'S MICHIGAN REGISTRATION NO. 10068
FOR STATE AND UNITED STATES AGENCIES.

DATE

SIGNED BY _____
CHIEF OF SURVEY PARTY
APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ ARELAC COUNTY