

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>20</u> N. S. R. <u>7</u> W.	<u>H-3, H-4, I-4, I-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 4-24- 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- H-3 Set by proportionate measurement between section corners. No sign of previous corner.
- H-4 Set corner at intersection of true 1/4 lines.
- I-4 Set this corner on line with existing monumentation on 1/4 line from East in Sec. 11 for latitude. Departure was fixed on line between section corners.
- I-5 Corner previously restored by J. Campbell, R.L.S. Renoted his witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3	H-4	I-4
Set DNR Monument	3' of 1" Pipe	Set DNR Monument
4" stem of trp Maple S36E 23.1'	4" W. Ash S50E 16.6'	6" Maple N82E 34.8'
6" Maple N83E 25.5'	7" Maple N61E 43.4'	8" Maple N46E 41.0'
30" Dia. Stone N53W 28.5'	7" Poplar N 1E 3.1'	6" Ash N10E 78.1'

I-5
Left 1/2" pipe w/RLS cap in place
6" Poplar S30W 56.3'
6" Ash S10E 40.6'

SIGNED BY Kenneth J. Ostling DATE 5-
SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____