

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>20</u> N. <u>8</u> R. <u>7</u> E. <u>X</u>	<u>G-3, G-4</u>
2. PROPERTY CONTROLLING IN SECTION <u>10</u>	T. <u>20</u> N. <u>8</u> R. <u>7</u> E. <u>W</u>	<u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION <u>10</u>	T. <u>20</u> N. <u>8</u> R. <u>7</u> E. <u>X</u>	<u>Bet. G-5, 10</u>
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 2-14 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 2-14 1973, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-3** Corner set by double proportionate measurement. No evidence of a previous corner.
- G-4** Set by proportionate measurement between section corners.
- Code 1** Set corner by standard survey procedure for subdivision of sections.
- Betw. G-5, 10** Set by standard procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<b>G-3</b>	<b>G-4</b>	<b>Code 1</b>
Set DNR Monument	Set DNR Monument	Set 3' of 1" pipe
8" W. Ash S30W 18.0'	6" Bl. Ash N20E 24.5'	4" Maple N 2W 6.0'
8" Bl. Cher. N70E 16.5'	12" Maple N60W 8.2'	4" Maple S77W 9.2'

**Betw. G-5, 10**  
 Set 2½' of 1" pipe  
 7" Maple S36E 27.0  
 9" Maple N85E 24.1



SIGNED BY Kenneth J. Ostling DATE 5-10  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_