

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>20</u> ^{N.} S. , R. <u>7</u> ^{E.} W.	<u>H-5</u>
2. PROPERTY CONTROLLING IN SECTION <u>10</u>	, T. <u>20</u> ^{N.} S. , R. <u>7</u> ^{E.} W.	<u>8, 11-15, 15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} S. , R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 4-24 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-5** **Set corner by proportionate measurement between section corners.**
- Code 8** **Set by standard procedure for the subdivision of sections.**
- 11-15** **Corner set to mark state property boundary.**
- 15** **Set corner by standard procedure for the subdivision of sections.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Code H-5	Code 15	Code 11-15
Drove 1/2" rerod in blacktop road	W 1/16 cor on S Sec. Line	M.P.O.L. between W 1/16 cor.
Face of P.P. S18W 53.1'	Drove 1/2" rerod in black top road.	on S Sec. Line & S 1/16 cor
7" Bl. Ash S78E 90.7'	Face of P.P. S 7W 60.0'	on W 1/16 line
	(not blazed)	3' of 1" pipe
	Maple N81W 117.6'	10" W. Ash S82E 5.3
		7" Maple S 8W 28.7
Code 8		
2 1/2' of 1" pipe		
8" Bl Cherry N53E 20.5'		
8" Maple S87W 23.8'		

SIGNED BY *Kenneth J. Ostling* DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____