

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>20</u> N. R. <u>7</u> E.	<u>J-4</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ S. _____ R. _____ E. _____ W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION <u>11</u>	T. <u>20</u> N. R. <u>7</u> E.	<u>Betw. 5 & J-4</u> <u>Betw. 2 & J-3</u> <u>Property Corner</u>
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 4-22 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 4-22 1973, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 1-4 **Set at intersection of N-S & E-W 1/4 lines by standard survey procedure.**
- betw 5 & J-4:
Set by standard procedure for the subdivision of section, 646.15 N of center 1/4 on N-S 1/4 line.
- betw 2 & J-3:
Corner set to mark state property boundary. Set 924.5 East of N 1/4 cor on N Sec.Line.
- prop. corner:
Corner set to mark state property boundary.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-4	Betw. 5 & J-4	Betw. 2 & J-3
Set 3' of 1" pipe	Set 3' of 1" pipe	Set 3' of 1" Pipe
8" W. Ash N88E 15.3'	9" Maple N45W 11.5	10" W. Ash S70E 7.0'
24" Tw W Ash N10E 12.6'	14" W ASH S45W 19.0	9" W. Ash N10W 8.0'
		3' of 1" pipe So. 66.0'
Property corner		
Set 3' of 1" pipe		
14" W. Ash N11W 10.2'		
7" W. Ash N73W 25.8'		

SIGNED BY Kenneth J. Ostling DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____