

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -	LOCATED IN -	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> N. <u>X</u> , R. <u>33</u> W. <u>X</u>	<u>B9, K2, K3</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See Below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner B9:** Found original B.T. Cedar 10" S33W 33 links.
 - Corner K3:** Found original B.T. Y. Birch 8" N77E 41 links.
 - Corner K2:** Found original B.T. Sugar 8" N72W 25 links. Now it is 23" and alive.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner B9:** Restored 9-10-80 from original B.T.
 - Corner K3:** Restored 10-19-81 from original B.T.
 - Corner K2:** Restored 10-19-81 from original B.T.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner B9:** Set 1" I.D.x32" iron pipe with 4" alum. cap.
16" Maple N69W 21.2 ft. 1/2S,NBT
 - Corner K3:** Set 1" I.D.x32" iron pipe with 4" alum. cap.
10" Cedar N09E 20.7 ft. S1,NBT
10" Spruce S70W 38.0 ft. S11,NBT
 - Corner K2:** Set 5/8"x2 ft. long iron pipe buried in woods road.
6" Sugar S58W 32.8 ft. 1/2S,NBT
8" Sugar N77E 36.1 ft. 1/2S,NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-26-82
CHIEF OF SURVEY PARTY
Keith L. Sackett
 MICHIGAN REGISTERED LAND SURVEYOR
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

