

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

	BARAGA COUNTY		
FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. 47 N. 33 E.	C11, D11	
2. PROPERTY CONTROLLING IN SECTION _____	29 T. 47 N. 33 E.	15	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See Below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner C11: Original monument and accessories not found.
 - Corner 15: Not set on original survey nor subsequently apparently.
 - Corner D11: Original monument and accessories not found. Corner falls in beaver pond.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner C11: Restored 4-21-81, on line between corners east and west and land calls north and south.
 - Corner 15: Established 4-22-81 on line between corners east and west.
 - Corner D11: Restored 4-22-81 on line between corners east and west. Corner falls in deep beaver pond.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner C11: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 - 7" White Birch N55W 15.9 ft. S30,NBT
 - 4" Maple S42W 17.3 ft. S31,NBT
 - 3" Maple S82E 24.7 ft. S32,NBT
 - Corner 15: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 - 4" White Birch S04W 12.2 ft. 1/16S,BT
 - 12" White Birch N62E 11.8 ft. 1/16S,BT
 - 4" Spruce N10W 28.6 ft. 1/16S,BT
 - Corner D11: Set 1"I.D.x36" iron pipe 229.81 ft. west of corner location for witness corner
 - Witnesses to witness pipe 24" White Birch N21W 18.7 ft. BT
 - 8" Yellow Birch S51E 19.7 ft. BT 10" Yellow Birch S03E 27.8 ft. BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-22-81
 CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

