

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

	BARAGA COUNTY	
FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. 47 N. R. 33 XX W.		B11, All
2. PROPERTY CONTROLLING IN SECTION 30, T. 47 N. R. 33 XX W.		15, 16
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 16, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner B11: Original monument and accessories not found.
 - Corner All: Original monument and accessories not found. Found Northern Paper Mills monument iron pipe with 2 1/4" brass cap.
 - Corner 15: Not set on original survey nor subsequently apparently.
 - Corner 16: Not set on original survey nor subsequently apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner B11: Restored on line and proportional distance between section corners east and west.
 - Corner All: Restored at Northern Paper Mills monument.
 - Corner 15: Established on line and proportional distance between corners east and west.
 - Corner 16: Established on line between corners east and west.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner B11: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 - 10" Yellow Birch S04E 24.0 ft. 1/4S,NBT
 - 8" Yellow Birch N32W 10.6 ft. 1/4S,NBT
 - 9" Sugar N69W 36.2 ft. 1/4S,NBT
 - Corner All: 1" I.D.by unknown length iron pipe with 2 1/4" brass cap.
 - 7" Sugar S10E 21.8 ft. S31,NBT
 - 6" Sugar S83W 9.7 ft.S36,NBT
 - Corner 15: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 - 14" Maple S12W 12.1 ft. 1/16S,BT
 - 5" Sugar S77E 7.6 ft. 1/16S,BT
 - 5" Sugar N02W 18.7 ft. 1/16S,BT
 - Corner 16: Set 1" I.D. x 32" iron pipe with 4" alum. cap.
 - 6" Maple S66W 7.8 ft. 1/16S,BT
 - 14" Balsam S11E 16.0 ft. 1/16S,BT
 - 3" Maple N56W 17.7 ft. 1/16S,BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-22-81
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

