

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	BARAGA COUNTY LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 47 N. <del>8</del> , R. 33 E. W.	F9
2. PROPERTY CONTROLLING IN SECTION 28	T. 47 N. <del>8</del> , R. 33 E. W.	7, 14
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See Below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner 7: Not set on original survey nor subsequently apparently.
- Corner 14: Not set on original survey nor subsequently apparently.
- Corner F9: Original monument and accessories not found.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner 7: Established 3-10-81 midway and on line between 1/4 corner south and section corner north.
- Corner 14: Established 3-11-81 midway and on line between 1/4 corner north and section corner south.
- Corner F9: Restored 3-16-81 midway and on line between section corners east and west.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Corner 7: Set 1" I.D.x32" iron pipe with 4" alum. cap.
  - 14" Spruce N70E 6.0 ft. 1/16S,BT
  - 12" Yellow Birch S23E 8.1 ft. 1/16S,BT
  - 14" Maple N34W 23.0 ft. 1/16S,BT
  - 4" Yellow Birch squared S45W 3.7 ft. marked 1/16, 28/27
- Corner 14: Set 1" I.D.x32" iron pipe with 4" alum. cap.
  - 4" Balsam N30E 13.8 ft. 1/16S,BT
  - 4" Balsam S57W 34.3 ft. 1/16S,BT
- Corner F9: Set 1" I.D.x32" iron pipe with 4" alum. cap.
  - 12" Sugar N08E 8.8 ft. 1/8S,NBT
  - 14" Sugar S53E 28.6 ft. 1/8S,NBT
  - 16" Yellow Birch S02W 8.3 ft. 1/8S,NBT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-22-81

CHIEF OF SURVEY PARTY  
*Keith L. Sackett*  
MICHIGAN REGISTERED LAND SURVEYOR  
Keith L. Sackett  
Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

