

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF-- | <u>BARAGA COUNTY</u> LOCATED IN-- | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>47</u> N. <u>W.</u> , R. <u>33</u> E. <u>W.</u> | <u>G11, F11</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>28</u> | T. <u>47</u> N. <u>W.</u> , R. <u>33</u> E. <u>W.</u> | <u>16</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. _____, R. _____ E. _____ | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 9, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner G11:** Original monument and accessories not found.
 - Corner 16:** Not set on original survey nor subsequently apparently.
 - Corner F11:** Original monument and accessories not found.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner G11:** Restored by double proportion distance between corners and land calls.
 - Corner 16:** Established on line midway between corners.
 - Corner F11:** Restored on line midway between corners.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner G11:** Set 1" I.D.x32" iron pipe with 4" alum. cap.
 - 6" Maple S50°W 18.5 ft. S33,NBT
 - 7" Maple S05°E 15.7 ft. S34,NBT
 - 7" White Birch N74°E 13.2 ft. S27, NBT
 - Corner 16:** Set 1" I.D.x32" iron pipe with 4" alum. cap.
 - 5" Tamarack N88°W 38.1 ft. 1/16S,BT
 - 3" Tamarack S63°E 12.8 ft. 1/16S,BT
 - Corner F11:** Set 1" I.D.x32" iron pipe with 4" alum. cap.
 - 3" Tamarack N12°E 12.2 ft. 1/4S,NBT
 - 3" Tamarack S70°W 13.5 ft. 1/4S,NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-22-81
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett (SEAL)
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006