

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

BARAGA COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> N. <u>W.</u> , R. <u>33</u> W.	<u>G9, E9, C9</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ S. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ S. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See Below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner G9: Original monument and accessories not found.
 - Corner E9: Original monument and accessories not found.
 - Corner C9: Original monument and accessories not found.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner G9: Restored 3-10-81 by double proportion distance between corners and land calls.
 - Corner E9: Restored 3-12-81 by double proportion distance.
 - Corner C9: Restored 3-16-81 on line between original $\frac{1}{4}$ corner west and original line tree east.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner G9: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 5" Yellow Birch S76°W 24.5 ft. S28,NBT
 4" Sugar N58°E 27.4 ft. S22,NBT
 6" Yellow Birch N16°W 23.4 ft. S21,NBT
 - Corner E9: Set 1" I.D. by 32" iron pipe with 4" alum. cap.
 6" Sugar N78°W 7.4 ft. S20,NBT
 8" Sugar N27°E 15.3 ft. S21,NBT
 16" Sugar S24°E 11.4 ft. S28,NBT
 - Corner C9: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 5" Sugar N12°E 4.9 ft. S19,NBT
 8" Spruce S50°E 18.6 ft. S29,NBT
 4" Sugar S26°W 8.5 ft. S30,NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-22-81
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006