

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF --: | BARAGA COUNTY LOCATED IN --: | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>47</u> N. <u>X</u> R. <u>33</u> W. <u>X</u> | E11 |
| 2. PROPERTY CONTROLLING IN SECTION <u>33</u> | T. <u>47</u> N. <u>X</u> R. <u>33</u> W. <u>X</u> | 15, 3 |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. _____ R. _____ E. _____ W. _____ | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 9, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner 15: Not set on original survey nor subsequently apparently.
 - Corner E11: Original monument and accessories not found.
 - Corner 3: Not set on original survey nor subsequently apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner 15: Established midway and on line between corners.
 - Corner E11: Restored by double proportion between corners and by land calls.
 - Corner 3: Established midway and on line between corners.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner 15: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 - 3" Tamarack N46°W 6.9 ft. 1/16S,BT
 - 3" Spruce S70°W 12.0 ft. 1/16S,BT
 - Corner E11: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 - 6" Spruce S30°E 7.6 ft. S33,NBT
 - 7" Spruce S55°W 11.5 ft. S32,NBT
 - 4" Maple N30°E 23.0 ft. S28,NBT
 - Corner 3: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 - Corner falls in Tamarack and Spruce swamp. No trees big enough for bearing trees.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-22-81
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006