

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T 47N R 33W	A10	_____
	T 47N R 33W	A11	_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jul 02 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


(A10) Quarter corner common to Section 25 T47N-R34W and Section 30 T47N-R33W. Corner reestablished in 1966 and recorded in 1969 by Billy D. Buckler, RLS. 1" pipe with 4" aluminum cap. 10" Hard Maple S42E 23.1', 10" Soft maple S43W 28.0'.
 (A11) Corner common to Sections 25&36 T47N-R34W and 30&31 T47N-R33W. Previously recorded in 1981 by K.L. Sackett, RLS as being monumented with a Northern Paper Mills monument and the following 1981 accessories: 7" Sugar S10E 21.8', 6" Sugar S83W 9.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A10) Recovered the 1966 monument, a 1" ID iron pipe with 4" alum. Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1966 NBTs. The Sugar SE is in good condition, the Maple SW is dead and down. Left the monument in place and made new witnesses as described below.
 (A11) Recovered the Northern Paper Mills monument, a 1" ID iron pipe capped with a brass tablet 2.25" inches in dia., appropriately stamped, in good condition, and at record bearing and distance from the 1981 accessories, both in good condition with overgrown blazes. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A10) Fd 1" ID pipe with 4" alum. cap. Blazed and scribed: 8" Sugar S76W 33.5' "1/4S NBT" 12" Maple N09W 29.3' do 12" Sugar N67E 7.4' do 13" Sugar S40E 22.9' (1980 NBT) Squared sugar post N16E 1.6' Bearings are magnetic. Distances are to notch in lower blaze.	(A11) Found 1" ID iron pipe with 2.25 dia. brass NPM tablet. Blazed and scribed the following: 6" Sugar N56E 17.4' "S30 NBT" 8" Sugar S55E 32.4' "S31 NBT" 10" Sugar S06E 21.7' the 1981 NBT 8" Sugar S88W 9.6' the 1981 NBT A squared sugar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/30/2001

for the Michigan Department of Natural Resources - Forest Management Division