

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 47N R 33W	E1
	T 47N R 33W	D5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

D5 Dec 30 2002
 E1 Dec 16 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(E1) Corner common to Sections 4-5 T47N-R33W and 32-33 T48N-R33W. Remonumented in 1959 by Billy D. Buckler RLS at the position of a scribed post recovered at record bearing and distance from the remains of W.Pine OBT N77E 62 links. Set 1" pipe with 4" brass cap. 8" Cedar N08W 146 links, 12" Cedar N08E 169 links.

(D5) Quarter corner common to Sections 8-17. 1852: Established by Francis Houck: Cedar 14 in diam. qr cor. Cedar 12 N68E 6 links. 1932: Record of Northern Paper Mills (NPM) states "Cole and Ellison found 14" Cedar N68E 6 standing dead. Set post". 1954: NPM record states "N. Peryam and S. Wickman found post, Cole's register. Probable Ced B.T. down. Set pipe at post. Ash 6 S15W 21.3, Red Map 8 N58E 29." 1965: Billy D. Buckler RLS states "This corner was placed at base of blown down Cedar which may have been corner tree. Stake marked B.T. in stump (Cedar) N68E 6 links which has faces but no iron marks visible. 1" iron pipe with 2" brass cap (Northern Paper Mills). 11/3/64. 8" S.Maple N58E 29 links, 6" B.Ash S20W 21 links. "

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E1) Recovered the 1959 monument under 18" of water in a beaver pond, in good condition, and at record bearing and distance from submerged W.Pine stump remains of what is probably the original BT noted above. Both 1959 Cedar NBTs were recovered in good condition, at record bearing and distance. Left the monument in place and made new witnesses as described below. A beaver lodge bears NW'ly about 25' distant.

(D5) Found the Northern Paper Mills monument laying nearly horizontally 6" below moss. Plumbed the monument to be in accord with the 1965 witness trees. The Maple is in good condition with scribing visible. The B.Ash is now a rotting stump.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E1) Found 1" I.pipe with 4" brass MI Dept. of Conservation cap. Blazed, scribed, and set measuring nails in:
 5" B.Spruce S25E 63.55' "S4 NBT"
 9" B.Spruce N41W 82.25' "S32 NBT"
 Distances are to nail with tag.
 14" Cedar N03W 96.3' old blazes
 17" Cedar N12E 111.0' old blazes
 Distances to C/L of tree. All bearings magnetic. Set sq'd cedar post adjacent.

(D5) Found 1" iron pipe with 2" brass Northern Paper Mills cap. Blazed, scribed, and set measuring nails in:
 9" Cedar S82E 27.0' "1/4S NBT"
 8" Cedar N80W 23.8' do
 9" Cedar N48W 39.3' do
 Distances are to nail with tag.
 The 1964 witness: 8" Maple N60E 19.1' with scribing visible. Bearings are magnetic. Set sq'd cedar post adjacent.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/16/03