

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 33W	E13
	T 46N R 33W	E1 in Iron Co.
	T _____ R _____	(same corner)
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 08/18/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E13) Corner common to Sections 32-33 T47N-R33W and 4-5 T46N-R33W. 1846 - Established by Austin Burt Deputy Surveyor. Y.Birch 18" Corner of Sections 32 and 33. 1852 - Francis Houck Deputy Surveyor marked Fir 12" S60E 7 links, Sugar 10" S60W 35 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E13) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner on the curved Township line and by single proportionate measurement to the original record between Section corner 15813.56' east and Township corner 10425.74' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 3" Balsam N23W 19.2' mrkd "S32 NBT"  
 3" Balsam S60E 21.8' "S4 NBT"  
 7" Sugar S01W 21.05' "S5 NBT"  
 7" Sugar N74W 19.3' "S32 NBT"  
 Set sq'd cedar post near. Bearings magnetic.



Signed by Stephan J. Szyszkoski Date 10/06/2009  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities