

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 33W	F13
	T 46N R 33W	F1 in Iron Co.
	T _____ R _____	(same corner)
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10					12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

T47N-R33W

I, Stephan J. Szyszkoski, in a field survey on 08/18/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F13) Quarter corner common to Section 33 T47N-R33W and Section 4 T46N-R33W. 1846 - Established by Austin Burt Deputy Surveyor. [Set post] Spruce 6" N12E 48 links, Fir 6" N18W 15 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F13) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner on the curved Township line and by single proportionate measurement to the original record between Section corner 13177.97' east and Township corner 13061.33' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap made firm in a mound of rock.
 Set measuring nail with MDNR tag in the side of:
 6" twin Maple N48E 20.65' mrkd "1/4S NBT"
 7" Maple N88E 26.95' do
 9" Maple S53E 30.55' do
 10" Spruce N59W 24.4' do
 Set sq'd cedar post near. Bearings magnetic.



Signed by Stephan J. Szyszkoski Date 10/06/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Revised Oct., 1995