

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> N. <u>34</u> R. <u>34</u> S. <u>W.</u>	I-13
2. PROPERTY CONTROLLING IN SECTION <u>35</u>	T. <u>47</u> N. <u>34</u> R. <u>34</u> S. <u>W.</u>	15
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ S. <u>W.</u>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 14, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner I-13: Original monument and accessories not found.
Corner 15: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner I-13: Re-established corner on line between corners east and west.
Corner 15: Established corner on line between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner I-13: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 9" Sugar N76°W 19.2' S34, NBT
 8" Sugar N89°E 16.0' S35, NBT
 8" Sugar S15°E 33.9' S 2, NBT
Corner 15: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 8" Sugar S20°E 25.2' 1/16S, BT
 6" Sugar S61°W 25.7' 1/16S, BT
 5" Sugar N71°E 24.7' 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett CHIEF OF SURVEY PARTY DATE _____
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

