

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> ^{N.} _{X.} R. <u>34</u> ^{X.} _{W.}	H-13
2. PROPERTY CONTROLLING IN SECTION <u>34</u>	T. <u>47</u> ^{N.} _{X.} R. <u>34</u> ^{X.} _{W.}	16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} _{S.} R. _____ ^{E.} _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner H-13: Original monument and accessories not found.

Corner 16: Not set on original survey nor subsequently apparently. Found old cedar post S8°W 59.4'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner H-13: Re-established 10/13/77 on line between corners east and west.

Corner 16: Established 10/14/77 on line between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H-13: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

9" Sugar N14°W 14.7' 1/4S, NBT
 4" Sugar S11°W 12.5' 1/4S, NBT
 6" Balsam S73°E 9.3' 1/4S, NBT

Corner 16: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

14" Cedar S68°E 11.3' 1/16S, BT
 9" Cedar N59°W 19.3' 1/16S, BT
 7" Cedar N31°E 23.2' 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 11/27/77
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

