

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 47 N. S., R. 34 W.	G-13
2. PROPERTY CONTROLLING IN SECTION 34	T. 47 N. S., R. 34 W.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 13, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner G-13: Original monument and accessories not found. Found old post which fits good with land calls and other corners. This post set prior to 1930.
- Corner 15: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner G-13: Re-established at old post.
- Corner 15: Established on line between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner G-13: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
- 7" Sugar S61°E 13.1' S3, NBT
 - 6" Sugar N47°E 11.4' S34, NBT
 - 10" Sugar N68°W 16.8' S33, NBT
- Corner 15: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
- 11" Sugar N20°W 3.9' 1/16S, BT
 - 10" Sugar S18°W 12.6' 1/16S, BT
 - 8" Sugar S42°E 33.7' 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett

DATE 11/23/77

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

