

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 34 W


Baraga COUNTY

DESCRIPTION OF CORNER Sec. Cor. 23, 24, 25, & 26

CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED September 3, 1968

WITNESSES TO CORNER..... Cedar 11 S48W 43 lks. "S26 NBT"



Cedar 6 S25E 64½ lks. "S25 NBT"

Black Spruce 11 N61E 28 lks. "S24 NBT"

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This monument placed at the site of a 2" x 4" x 6' squared cedar post, which is about 40.13 chains South of an original corner to the North, about 40.16 chains West of an original corner to the East, and about 39.62 chains East of an original corner to the West. Relationship to corners to South is not known. Found points of two older cedar posts in the muck and the rotted off uppers of these posts lying buried in the moss at different levels. It is possible that one of these is the original post, but the species used is not described in the original field notes. Old blazes and register trees near corner indicate use for an estimated 75 years or more.

Names of persons present when monument was placed: A. O. Enger, K. L. Sackett, J. E. Hulkonen, and W. A. Dellies.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

10/29/68