

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46-47 N.R. 34W


Baraga COUNTY

DESCRIPTION OF CORNER Section corner 1, 2, 35 & 36

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 29, 1968

WITNESSES TO CORNER..... Cedar 15 S11E 42 lks. "S1 NBT"



Cedar 14 S73W 62 lks. "S2 NBT"

Red Maple 15 N11 $\frac{1}{2}$ E 63 lks. "S36 NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner set at site of an old 4" x 4" x 6' squared and scribed cedar post set by unknown surveyor from an original BT, Y. Birch 16 N44W 57, now a dead stub about 20 ft. high with scars over upper and lower faces, but rotted out inside. Found points of two older posts, one of which appears to have been the original cherry post, in the ground at the foot of the first described post. Many blazes with old, illegible writing on them in vicinity. Corner agrees with chainages and line from original corners 1 mile East and 1/2 mile West.

Names of persons present when monument was placed: A. O. Enger, J. E. Hulkonen, and W. A. Dellies.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

11/26/68