

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46-47 N.R. 34W


Baraga COUNTY

DESCRIPTION OF CORNER 1/4 cor. between Sec. 1 & 36

CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 29, 1968

WITNESSES TO CORNER..... Red Maple 14 N 5W 64½ lks. "½S NBT"



Cedar 14 S24W 71 lks. "½S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed midway on line between original Section corners 40.105 chains to East and West, as measured by survey crew under the direction of B. D. Buckler, R.L.S. No visible evidence of original corner or accessories, but an old square post and iron pipe were found S17E 15½ links from corner set here, placed there by unknown parties, and of unknown history. An old register tree with illegible names stands WSW of and facing monument placed by the undersigned.

Names of persons present when monument was placed: A. O. Enger, J. E. Hulkonen, and Warren Dellies.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

11/26/68