

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. T47N N.R. 33-34W


Baraga COUNTY

DESCRIPTION OF CORNER 1/4 cor. between Sec. 31 & 36

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED August 28, 1968

WITNESSES TO CORNER..... Black Spruce 6 S86E 50 lks. "1/4 S NBT"



Balsam Fir 4 N46E 106 1/2 lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument set from two probable cedar BT's: Cedar 10 S62W 21 is a 4 ft. high stub with overgrowth scar facing corner, but faces and marks have been burned; Cedar 8 N77E 39 is down and badly rotted, but old choppings are evident on side that faced corner.

Corner found off random transit line on East side of Sec. 36, N88 1/2 W 25 1/2 links from 40.00 chain marker from an original corner 1/2 mile South.

Found scraps of what appeared to be an old cedar post in the muck and water at the corner location.

Names of persons present when monument was placed: A. O. Enger, J. E. Hulkonen, and W. A. Dellies.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

11/26/68