

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 34W


Baraga COUNTY

DESCRIPTION OF CORNER 1/4 corner on North side Section 6

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 31, 1966

WITNESSES TO CORNER..... 9" Hard Maple (1/4 S NBT) N49°W 28.5'



9" Hard Maple (1/4 S NBT) S43°E 8.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at an old fence corner. Found Y. Birch (green) bearing N3°W 29 lks. and a Y. Birch stump, bearing N47°E 44 lks. Found bottom of wood stake in soil.

Corner lies 40 lks. West of an old log road.

Fence bears North and West from corner.

SURVEYOR'S SEAL

SIGNED Billy O. Buckler DATE 3/29/66  
REGISTERED LAND SURVEYOR