

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 34W


Baraga COUNTY

DESCRIPTION OF CORNER 1/4 cor. between Sec. 24 & 25

CORNER MONUMENT 1" I. D. x 36" iron pipe with 2" brass cap

DATE MONUMENT PLACED AND WITNESSED August 30, 1968

WITNESSES TO CORNER..... Cedar 7 N16W 12 lks. "1/4S NBT"



CIRCLE CORNER REGISTERED

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-witnessed the above monument as placed by Northern Paper Mills personnel, probably in early 1950's. Corner had been set from an original BT, Tam. 12 S3E 6. Stump still in place, badly rotted, no identifying marks left, but there may have been some when corner was set. Also found scraps of an old cedar post in the muck, possibly the original post, and a more recent squared cedar post. Also found a 1 1/4" I. D. iron pipe at corner, set by unknown surveyor. A 3/4" I. D. iron pipe bearing an aluminum plug marked WMPCo. No. 57, 1931, is located S82W 84 links from corner.

Northern Paper Mills had re-witnessed corner as follows:

Cedar 10 S32 1/2 W 52 1/2 lks. "1/4 S, S25, BT"
Cedar 12 N24 W 57 1/2 lks. "1/4 S, S24, BT"

Names of persons present on this date when corner was re-witnessed: A. O. Enger, J. E. Julkonen, W. A. Dellies.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

10/29/68