

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47-48 N.R. 34 W


Baraga COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 3-4, T47N R34W and 33-34 T48N R34W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/27/65 with Forester Stevens

WITNESSES TO CORNER..... 14" Cedar (S3 NBT), S 28° E, 25½ lks.



17" H. Maple (S34 NBT), N 06° E, 43 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from two (2) Original BT's (Hemlock 7" N 35½° W, 20 lks.) notch and scribe mark on Lower face. Hemlock to SE, a stump badly rotted checks good in bearing and distance.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 9/13/1965
Frank J. Bray
REGISTERED LAND SURVEYOR