

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 48-47 N.R. 34 W


Baraga COUNTY

DESCRIPTION OF CORNER W 1/16 for Secs. 3, T47N R34W and 34, T48N R34W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/28/65 with Forester Stevens

WITNESSES TO CORNER..... 12" Cedar (W 1/16 BT), N 10° W, 21 lks.



6" E. Maple (W 1/16 BT), S 04° W, 40 lks.

Bearings and Distances are to Monument

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This Corner was placed 2 lks. South of being on line between Section Corner to West and 1/4 Corner to East. Corner was placed midway between Corners mentioned above. Corner was placed 2 lks South because of Large Boulder.

**SURVEYOR'S SEAL**

SIGNED Frank J. Bray  
Frank J. Bray  
REGISTERED LAND SURVEYOR

DATE 2/10/1966