

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> N. <u>W.</u> R. <u>34</u> E. <u>W.</u>	<u>I-11, I-12</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 16, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner I-11: Original monument and accessories not found. Found old Northern Paper Mills location poster on 16" cherry - N53E, 12.1 ft. Numerous old blazes in area.

Corner I-12: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner I-11: Re-established from land calls and other corners in area. Location has been used since 1920's.

Corner I-12: Re-established on line between section corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner I-11: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 24" W. Pine N54°W 36.0 ft. S27, NBT
 6" Maple N76°E 10.7 ft. S26, NBT
 7" Spruce S53°E 45.9 ft. S35, NBT

Corner I-12: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 6" Maple S48°E 32.1 ft. ½S, NBT
 10" Cherry S83°W 20.6 ft. ½S, NBT
 7" Elm N26°E 24.5 ft. ½S, NBT

Corner falls ½ chain east and 1 chain south of old log road.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett

DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

