

BARAGA Co.

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY... T. 47 N. 34 W. G11
2. PROPERTY CONTROLLING IN SECTION 34, T. 47 N. 34 W. 9, 1
3. MISCELLANEOUS PROPERTY IN SECTION... T. ... N. S., R. ... E. W.
4. LOT NO. ... RECORDED PLAT
5. PRIVATE CLAIMS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 20, 1978, established...

- A. Description of original monument and accessories and/or subsequent restoration:
Corner 9: Not set on original survey or subsequently apparently.
Corner G11: Found Northern Paper Mills' monument with 2" brass cap. Also found original bearing Cedar 10" N51E 18 lks.
Corner 1: Not set on original survey or subsequently apparently.
B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner 9: Established 1-20-78 on subdivision of section.
Corner G11: Re-establish 1-19-78 at monument.
Corner 1: Established 1-19-78 on subdivision of section.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner 9: Set 1" I.D. x 3/8" Iron Pipe with 4" aluminum cap.
5" Spruce S4W 13.6 ft. 1/16S, BT
5" Spruce N79W 34.8 ft. 1/16S, BT
4" Spruce N29E 26.4 ft. 1/16S, BT
Corner 1: Set 1" I.D. x 3/8" Iron Pipe with 4" aluminum cap
6" Sugar S13E 2.9 ft. 1/16S, BT
7" Sugar N41W 13.1 ft. 1/16S, BT
7" Sugar N20E 29.2 ft. 1/16S, BT
Corner G11: 1" I.D. x Unknown length Iron Pipe with 2" brass cap by Northern Paper Mills
7" Cedar N53W 9.2ft. S28, NBT
5" Cedar S19E 32.2 ft. S34, NBT
10" Cedar S32W 38.8 ft. S33, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett, Michigan Registered Land Surveyor, Department of Natural Resources. DATE July 7, 1978.

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

