

BARAGA Co.

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY T. 47 N. 34 W. H12, H11
2. PROPERTY CONTROLLING IN SECTION 34, T. 47 N. 34 W. 5, 8
3. MISCELLANEOUS PROPERTY IN SECTION T. N. S., R. E. W.
4. LOT NO., RECORDED PLAT
5. PRIVATE CLAIMS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 19, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law.

- A. Description of original monument and accessories and/or subsequent restoration:
Corner H12: Not set on original survey or subsequently apparently.
Corner 5: Not set on original survey or subsequently apparently.
Corner 8: Not set on original survey or subsequently apparently.
Corner H11: Original Monument and Accessories Not Found.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner H12: Established on Section Subdivision.
Corner 5: Established on Section Subdivision.
Corner 8: Established on Section Subdivision.
Corner 11: Re-established on Section Subdivision. Found old squared 12" cedar N61E 6.0 ft. Numerous other blazes and signature trees in area. Position also fits with original corners east and west.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner H12: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap
8" Sugar S36W 11.2 ft. 1/4S, BT
5" Sugar N64W 21.7 ft. 1/4S, BT
26" Sugar N76E 19.3 ft. 1/4S, BT
Corner 5: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap
8" cedar S24E 12.8 ft. 1/16S, BT
6" Cedar N35W 15.3 ft. 1/16S, BT
5" Cedar N24E 16.4 ft. 1/16S, BT
Corner 8: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap
8" Sugar N55E 26.6 ft. 1/16S, BT
5" Sugar S18W 15.4 ft. 1/16S, BT
8" Sugar N13W 25.4 ft. 1/16S, BT
Corner H11: Set 1" I.D.x36" Iron Pipe with 4" Aluminum Cap
6" Cedar S11W 23.1 ft. 1/4S, NBT
7" Cedar N65W 41.6 ft. 1/4S, NBT
8" Cedar N24E 11.1 Ft. 1/4S, NBT

SIGNED BY DATE

SURVEYOR'S MICHIGAN REGISTRATION NO.

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY DATE

APPROVED AND SIGNED BY DATE

CHIEF OF SURVEY PARTY
Keith L. Sackett
MICHIGAN REGISTERED LAND SURVEYOR
Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

