

BARAGA Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 47 N. S. R. 34 E. W.	F12, D11
2. PROPERTY CONTROL- 33 ING IN SECTION _____	T. 47 N. S. R. 34 E. W.	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See Below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner F12: Not set on original survey nor subsequently apparently.
 - Corner 3: Not set on original survey nor subsequently apparently.
 - Corner D11: Original monument and accessories not found. Found old blazed line south. Also old Northern Paper Mills location poster west.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner F12: Established 12-18-78 on Section subdivision.
 - Corner 3: Established 12-5-78 on line between corners north and south.
 - Corner D11: Restored on 11-29-78 by double proportion.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner F12: Set 1" I.D.x36" I.P. with alum. cap broke off.
 - 18" Sugar N53W 5.4 ft. 1/4S, BT
 - 14" Sugar N69E 9.1 ft. 1/4S, BT
 - 12" Sugar S39W 26.5 ft. 1/4S, BT
 - Corner D11: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap.
 - 9" Spruce S31E 11.1 ft. S33, NBT
 - 4" Balsam S12W 7.4 ft. S32, NBT
 - 7" Spruce N20W 38.4 ft. S29, NBT
 - Corner 3: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap.
 - 16" Cedar S30E 17.3 ft. 1/16S, BT
 - 6" Cedar N73W 21.8 ft. 1/16S, BT
 - 8" Cedar N14W 15.5 ft. 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 2-12-79
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

